



1. FINISH GRADE IN PLANTER 3 INCHES BELOW BOX
2. RECTANGULAR VALVE BOX W/LOCKING SS BOLT - HEAT BRAND "PB" ON LID
3. APPROVED WIRE CONNECTORS
4. 36-INCH EXPANSION COILS
5. FINISH GRADE IN TURF 1 INCH BELOW BOX
6. NATIVE SOIL COMPACTED TO ORIGINAL DENSITY
7. PVC CONDUIT SWEEP FOR IRRIGATION CONTROL WIRING (WHEN SPECIFIED)
8. 3 CU. FT. 3/4-INCH GRAVEL

NOTES:

- A. ALL WIRING MUST CONFORM TO LOCAL CODES.
- B. PROVIDE 24 INCHES EXPANSION COILS AT EACH WIRE CONNECTION.
- C. PROVIDE 3-INCH CLEARANCE BETWEEN WIRES AND BOX.
- D. EPOXY ALL GAPS BETWEEN WIRE AND CONDUIT AT EXPOSED SWEEP ENDS.
- E. PROVIDE 4 EA. CONCRETE BRICKS UNDER VALVE BOX (TYP.).
- F. NO WIRE SPLICES SHALL BE ALLOWED UNLESS APPROVED BY THE CITY
- G. ALL SPARE WIRES FOR END RUN SHALL BE IN A PULL BOX TYP. AND SHALL BE LABELED IN BOX AND AT CONTROLLER.
- H. PROVIDE PULL BOX FOR ALL WIRE SPLICES FOR RUNS OVER 2500 FEET OR AS APPROVED BY CITY.

SECTION
NO SCALE

APPROVED BY:

Jonathan George Smith

4/24/15

DIRECTOR OF PUBLIC WORKS
JONATHAN GEORGE SMITH

DATE



CITY OF MENIFEE

PULL BOX

REVISION	BY:	APPROVED	DATE

STANDARD PLAN NO. 1302.18 SHEET 1 OF 1