



- 1. TREE OR SHRUB
- 2. ORIGINAL SLOPE
- 3. ROOT CROWN
- 4. PERMANENT BERM / 3-INCH HEIGHT
- 5. 1:1 SLOPE (MAXIMUM)
- 6. BACKFILL MIX - REFER TO SPECIFICATIONS
- 7. ROOT BALL - SET ON FIRM NATIVE SOIL
- 8. FERTILIZER TABLETS - REFER TO SPECIFICATIONS. (8-INCH DEPTH MAXIMUM)
- 9. SLOPE BOTTOM OF PLANT PIT
- 10. TWO TIMES DIAMETER OF ROOT BALL (MINIMUM)
- 11. DEPTH OF ROOT BALL (MINUS 1-INCH)
- 12. MULCH (3-INCH DEPTH MIN.) - REFER TO SPECIFICATIONS FOR MATERIAL

**SECTION  
NO SCALE**

**NOTES:**

- A. SLASH ROOTBALL VERTICALLY ON FOUR SIDES (1-INCH DEEP) PRIOR TO PLANTING.
- B. TAMP BACKFILL MIX LIGHTLY TO REMOVE AIR POCKETS IN THE SOIL.
- C. MAINTAIN 6-INCH RADIUS (MIN.) AROUND PLANT TRUNK CLEAR OF MULCH.
- D. FOR NATIVE SPECIES, ELIMINATE MULCH IN PLANT PIT AREA.

APPROVED BY:

*Jonathan George Smith*

4/24/15

DIRECTOR OF PUBLIC WORKS  
JONATHAN GEORGE SMITH

DATE



**CITY OF MENIFEE**

**TREE OR  
SHRUB PLANTING  
(ON SLOPE)**

REVISION	BY:	APPROVED	DATE