



1. VINYL TREE TIES - NAIL TO TREE STAKES (4 REQUIRED)
2. TREE TRUNK
3. LODGEPOLE STAKES (2) - 10 FEET LONG X 2-INCH DIAMETER (MIN.)
4. ROOT CROWN SET 1-INCH ABOVE FINISH GRADE (MIN.)
5. TEMPORARY WATERING BASIN AND BERM
6. FINISH GRADE
7. ROOT BALL - SET ON FIRM NATIVE SOIL
8. BACKFILL MIX - REFER TO SPECIFICATIONS
9. FERTILIZER TABLETS - REFER TO SPECIFICATIONS (8-INCH DEPTH MAX.)
10. PLANT PIT - SCARIFY SIDES AND BOTTOM
11. TWO TIMES DIAMETER OF ROOT BALL (MINIMUM)
12. 12 INCHES DEPTH (MIN.) INTO NATIVE SOIL BELOW ROOTBALL
13. DEPTH OF ROOT BALL - MINUS 1-INCH
14. MULCH - REFER TO SPECIFICATIONS (3-INCH DEPTH MIN.)

**SECTION
NO SCALE**

NOTES:

- A. REMOVE WATERING BASIN PRIOR TO END OF MAINTENANCE PERIOD.
- B. SLASH ROOT BALL VERTICALLY ON FOUR SIDES (1-INCH DEEP) PRIOR TO PLANTING.
- C. SINGLE STAKE 5 GALLON TREES DOUBLE STAKE 15 GALLON TREES.
- D. TAMP BACKFILL MIX LIGHTLY TO REMOVE AIR POCKETS IN SOIL.
- E. IN AREAS WITH HIGH WINDS, 3-INCH DIAMETER STAKES AND / OR V.I.T. TWIST BRACES MAY BE REQUIRED - REFER TO SPECIFICATIONS.
- F. MAINTAIN 6" CLEARANCE (MIN.) AROUND TREE TRUNK CLEAR OF MULCH.

APPROVED BY:

Jonathan George Smith

4/24/15

DIRECTOR OF PUBLIC WORKS
JONATHAN GEORGE SMITH

DATE



CITY OF MENIFEE

**TREE PLANTING
AND STAKING
(5-15 GALLON)**

REVISION	BY:	APPROVED	DATE

STANDARD PLAN NO. 1303.05 SHEET 1 OF 1